

Nemko Test Report: 1L0025RUS1

Applicant: Andrew Corporation

Equipment Under Test: InCell Fiber Optic Distributed Antenna System
Model: SMR Repeater

FCC ID: KUWINCELLSMR

In Accordance With: **FCC Part 90, Subpart I**
Private Land Mobile Repeater

Tested By: Nemko Dallas Inc.
802 N. Kealy
Lewisville, TX 75057-3136

Authorized By:



Tom Tidwell, Wireless Group Manager

Date: February, 2001

Total Number of Pages: 34

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Table of Contents

Section 1.	Summary of Test Results	3
Section 2.	General Equipment Specification.....	5
Section 3.	RF Power Output.....	7
Section 4.	Occupied Bandwidth	8
Section 5.	Spurious Emissions at Antenna Terminals	9
Section 6.	Field Strength of Spurious Emissions.....	14
Section 7.	Frequency Stability	23
Section 8.	Test Equipment List	24
ANNEX A - TEST METHODOLOGIES		25
ANNEX B - TEST DIAGRAMS		31

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Section 1. Summary of Test Results

Manufacturer: Andrew Corporation

Model No.: InCell SMR Repeater

Serial No.:

General: **All measurements are traceable to national standards.**

These tests were conducted on a sample of the equipment for the purpose of demonstrating compliance with FCC Part 90, Subpart I.



New Submission



Production Unit



Class II Permissive Change



Pre-Production Unit



Equipment Code

THIS TEST REPORT RELATES ONLY TO THE ITEM(S) TESTED.

THE FOLLOWING DEVIATIONS FROM, ADDITIONS TO, OR EXCLUSIONS FROM THE TEST SPECIFICATIONS HAVE BEEN MADE.

See " Summary of Test Data".

**NVLAP LAB CODE: 100426-0**

NEMKO Dallas Inc. authorizes the above named company to reproduce this report provided it is reproduced in its entirety and for use by the company's employees only.

Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. NEMKO Dallas Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report. This report applies only to the items tested.

EQUIPMENT: InCell SMR Repeater**PROJECT NO.:** 1L0025RUS1**Summary Of Test Data**

NAME OF TEST	PARA. NO.	SPEC.	MEAS.	RESULT
RF Power Output	90.205		19.7 dBm	Complies
Audio Frequency Response	TIA EIA-603.3.2.6	N/A	N/A	N/A
Audio Low-Pass Filter Response	TIA EIA-603.3.2.6	N/A	N/A	N/A
Modulation Limiting	TIA EIA-603.3.2.6	N/A	N/A	N/A
Occupied Bandwidth	90.210	Plots	Plots	Complies
Spurious Emissions at Antenna Terminals	90.210	Plots	Plots	Complies
Field Strength of Spurious Emissions	90.210	-13 dBm	> -13 dBm	Complies
Frequency Stability	90.213	N/A	N/A	N/A
Transient Frequency Behavior	90.214	N/A	N/A	N/A

Footnotes For N/A's:

- (1) Since the E.U.T. does not contain modulation circuitry modulation testing was not performed.
- (2) Since the E.U.T. is not a keyed carrier system, Transient Frequency Behavior was not performed.

EQUIPMENT: InCell SMR Repeater**PROJECT NO.:** 1L0025RUS1**Section 2. General Equipment Specification****Transmitter**

Supply Voltage Input:	CDU RAU	120 VAC via power mains 24 Vdc via CDU			
Frequency Range:	851-869 MHz				
Tunable Bands:	851-869 MHz				
Type(s) of Modulation:	F3E (Voice) <input checked="" type="checkbox"/>	F1D <input type="checkbox"/>	F2D <input type="checkbox"/>	D7W (QAM) <input type="checkbox"/>	D7W (IDEN) <input checked="" type="checkbox"/>
Gain:	15 dB				
Maximum Input:	0 dBm				
Output Impedance:	50 Ohms				
RF Power Output (rated):	Voice: +14 dBm (.024 W) iDEN: +20 dBm (.100 W)				
Operator Selection of Operating Frequency:	Not selectable				
Power Output Adjustment Capability:	Not adjustable by user				
Frequency Translation:	F1-F1 <input checked="" type="checkbox"/>	F1-F2 <input type="checkbox"/>	N/A <input type="checkbox"/>		
Band Selection:	Software <input type="checkbox"/>	Duplexer Change <input type="checkbox"/>	Fullband Coverage <input checked="" type="checkbox"/>		

EQUIPMENT: InCell SMR Repeater**PROJECT NO.:** 1L0025RUS1**Modifications Made During Testing**

None


System Description

The EUT is a SMR band repeater system that uses fiber optic to distribute modulated rf signals from a base station or repeater to locations throughout a building. The system operates with a direct connection in the uplink direction.

The system is made up of two components:

- 1) CDU (Central Distribution Unit) - This unit is typically located in a wiring closet. Each CDU can interface to six RAU (Remote Antenna Units). The CDU collects and distributes voice and data signals through fiber cable pairs. The CDU connects to the output of a repeater unit. The Uplink direction is a directly wired connection and cannot connect directly to an antenna. The transmit signals from the repeater are converted from rf to optical and distributed via the fiber cables to a RAU.
- 2) RAU (Remote Antenna Unit) - This unit converts the signal received from the CDU back to rf and transmits the rf to subscriber units within its coverage range. Conversely it receives the rf signals transmitted by the subscriber units, converts the rf to an optical signal and sends it to the CDU via fiber.

The overall rf gain of the system in the downlink direction is nominally 15 dB.

System Diagram

EQUIPMENT: InCell SMR Repeater**PROJECT NO.:** 1L0025RUS1**Section 3. RF Power Output**

NAME OF TEST: RF Power Output

PARA. NO.: 2.985

TESTED BY: David LightTom Tidwell & Debbie Jensen

DATE: 15 Feb 2001

Test Results: Complies.**Measurement Data:**

IDEN Modulation

Frequency (MHz)	Measured Power (dBm)
852	11.0
860	13.3
868	13.8

Voice Modulation

Frequency (MHz)	Measured Power (dBm)
852	19.2
860	19.7
868	19.6

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Section 4. Occupied Bandwidth

NAME OF TEST: Occupied Bandwidth	PARA. NO.: 2.989
TESTED BY: David LightTom Tidwell & Debbie Jensen	DATE:15 Feb 2001

Test Results: Complies.

Test Data: See attached graph(s).

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Test Data - Occupied Bandwidth



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot Occupied Bandwidth


Page 1 of 4

Complete XPreliminary

Job No.: 1L0025R Date: 02/15/01
Specification: PART 90 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 50
E.U.T.: INCELL SMR REPEATER
Configuration: TX FULL POWER
Sample No.: S02
Location: Lab 1 RBW: REFER TO PLOTS
Detector Type: Peak VBW: REFER TO PLOTS

Test Equipment Used

Antenna: Directional Coupler:
Pre-Amp: Cable #1: 1082
Filter: Cable #2:
Receiver: 1036 Cable #3:
Attenuator #1: 1475 Cable #4:
Attenuator #2: Mixer:
Additional equipment used:
Measurement Uncert: +/-3.6 dB



Date: 15.FEB.2001 10:36:02

Notes: OUTPUT SIGNAL - iDEN

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Test Data - Occupied Bandwidth



Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.

Data Plot Occupied Bandwidth

Page 2 of 4

Job No.: 1L0025R Date: 02/15/01
Specification: PART 90 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 50
E.U.T.: INCELL SMR REPEATER
Configuration: TX FULL POWER



Date: 15.FEB.2001 10:41:58

Notes: INPUT SIGNAL - iDEN

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Test Data - Occupied Bandwidth



Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.

Data Plot Occupied Bandwidth

Page 3 of 4

Job No.: 1L0025R Date: 02/15/01
Specification: PART 90 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 50
E.U.T.: INCELL SMR REPEATER
Configuration: TX FULL POWER



Date: 15.FEB.2001 10:47:08

Notes: OUTPUT SIGNAL - VOICE

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Test Data - Occupied Bandwidth



Nemko Dallas, Inc.


Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Test Plot: Occupied Bandwidth

Page 4 of 4

Job No.: 1L0025R Date: 02/15/01
Specification: PART 90 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 50
E.U.T.: INCELL SMR REPEATER
Configuration: TX FULL POWER



Notes: INPUT SIGNAL - VOICE

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Section 5. Spurious Emissions at Antenna Terminals

NAME OF TEST: Spurious Emissions @ Antenna Terminals	PARA. NO.: 2.991
TESTED BY: David LightTom Tidwell & Debbie Jensen	DATE: 15 Feb 2001

Test Results: Complies.

Test Data: See attached graph(s).

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Test Data - Spurious Emissions at Antenna Terminals



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot Intermodulation Characteristics


Page 1 of 2

Complete X
Preliminary _____

Job No.: 1L0025R Date: 02/15/01
Specification: PART 90 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 50
E.U.T.: INCELL SMR REPEATER
Configuration: TX 3 SIGNALS FULL POWER
Sample No.: S02
Location: Lab 1 RBW: 30 kHz
Detector Type: Peak VBW: 30 kHz

Test Equipment Used

Antenna: _____ Directional Coupler: _____
Pre-Amp: _____ Cable #1: 1082
Filter: _____ Cable #2: _____
Receiver: 1036 Cable #3: _____
Attenuator #1: 1475 Cable #4: _____
Attenuator #2: _____ Mixer: _____
Additional equipment used: _____
Measurement Uncertainty: +/-3.6 dB



Date: 15.FEB.2001 11:25:24

Notes: MARKER 1 INDICATES OUT OF BAND INTERMODULATION
MARKER 2 INDICATES INBAND INTERMODULATION
iDEN Modulation

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Test Data - Spurious Emissions at Antenna Terminals




Dallas Headquarters:
802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.

Data Plot Intermodulation Characteristics

Page 2 of 2

Job No.: 1L0025R Date: 02/15/01
Specification: PART 90 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 50
E.U.T.: INCELL SMR REPEATER
Configuration: TX 3 SIGNALS FULL POWER



Date: 15.FEB.2001 11:36:59

Notes: **MARKER 1 INDICATES OUT OF BAND INTERMODULATION**
MARKER 2 INDICATES INBAND INTERMODULATION
Voice Modulation

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Test Data - Spurious Emissions at Antenna Terminals



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot Antenna Port Spurious Emissions


Page 1 of 4

Complete XPreliminary

Job No.: 1L0025R Date: 02/15/01
Specification: PART 90 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 50
E.U.T.: INCELL SMR REPEATER
Configuration: TX FULL POWER
Sample No.: S02
Location: Lab 1 RBW: Refer to plots
Detector Type: Peak VBW: Refer to plots

Test Equipment Used

Antenna: Directional Coupler:
Pre-Amp: Cable #1: 1082
Filter: Cable #2:
Receiver: 1036 Cable #3:
Attenuator #1: 1475 Cable #4:
Attenuator #2: Mixer:
Additional equipment used:
Measurement Uncertainty: +/-3.6 dB



Notes: MARKER 1 INDICATES CARRIER
MARKER 2 INDICATES EMISSION
Voice modulation

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Test Data - Spurious Emissions at Antenna Terminals



Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.

Data Plot Antenna Port Spurious Emissions

Page 2 of 4

Job No.: 1L0025R Date: 02/15/01
Specification: PART 90 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 50
E.U.T.: INCELL SMR REPAETER
Configuration: TX FULL POWER



Date: 15.FEB.2001 11:51:09

Notes: Voice Modulation

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Test Data - Spurious Emissions at Antenna Terminals



Dallas Headquarters:


802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Nemko Dallas, Inc.

Data Plot Antenna Port Spurious Emissions

Page 3 of 4

Job No.: 1L0025R Date: 02/15/01
Specification: PART 90 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 50
E.U.T.: INCELL SMR REPAETER
Configuration: TX FULL POWER



Date: 15.FEB.2001 15:21:50

Notes: MARKER 1 INDICATES CARRIER
MARKER 2 INDICATES EMISSION
iDEN Modulation

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Test Data - Spurious Emissions at Antenna Terminals




Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667**Test Plot: Antenna Port Spurious Emissions**

Page 4 of 4

Job No.: 1L0025R Date: 02/15/01
Specification: PART 90 Temperature(°C): 22
Tested By: David Light Relative Humidity(%) 50
E.U.T.: INCELL SMR REPAETER
Configuration: TX FULL POWER



Date: 15.FEB.2001 15:22:52

Notes: iDEN Modulation

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Section 6. Field Strength of Spurious Emissions

NAME OF TEST: Field Strength of Spurious Emissions	PARA. NO.: 2.993
TESTED BY: David LightTom Tidwell & Debbie Jensen	DATE: 16 Feb 2001

Test Results: Complies.

Test Data: See attached table.

Note: See page A5 for applicable limit.

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Test Data - Radiated Emissions



Nemko Dallas, Inc.

Dallas Headquarters:

 802 N. Kealy
 Lewisville, TX 75057
 Tel: (972) 436-9600
 Fax: (972) 436-2667

Field Strength of Spurious Emissions

Page 1 of 1

Job No.: 1L0025R Date: 2/16/01 Complete X
 Preliminary _____

Specification: PART 90 Temperature(°C): 22
 Tested By: David Light Relative Humidity(%): 50
 E.U.T.: INCELL SMR REPEATER
 Configuration: TX FULL POWER MID BAND
 Sample Number: S02
 Location: AC 3 RBW: 1 MHz Measurement
 Detector Type: Peak VBW: 500 kHz Distance: 3 m

Test Equipment Used

Antenna: Directional Coupler:
 Pre-Amp: 1016 Cable #1: 1484
 Filter: Cable #2: 1485
 Receiver: 1464 Cable #3:
 Attenuator #1: Cable #4:
 Attenuator #2: Mixer:
 Additional equipment used:
 Measurement Unc +/-3.6 dB

Frequency (MHz)	Meter Reading (dBm)	Correction Factor (dB)		Pre-Amp Gain (dB)	Substitution Antenna Gain (dBd)		ERP (dBm)	ERP (mW)	Polarity	Comments
1720	-46.7	29.9		32.9	6.4		-43.4	0.000046	V	
2580	-53.7	35.6		33.3	8.0		-43.5	0.000045	V	
3440	-54.8	37.1		33.6	8.1		-43.2	0.000048	V	
4300	-61.2	42.8		33.2	7.9		-43.7	0.000043	V	
5160	-62.5	40.6		32.8	9.1		-45.6	0.000027	V	NOISE FLOOR
6020	-63.7	37.9		32.0	9.5		-48.3	0.000015	V	NOISE FLOOR
6880	-66.0	38.3		32.8	10.1		-50.4	0.000009	V	NOISE FLOOR
7740	-65.5	40.4		33.4	9.4		-49.0	0.000012	V	NOISE FLOOR
8600	-63.7	40.3		34.4	9.9		-47.9	0.000016	V	NOISE FLOOR
1720	-47.0	32.7		32.9	6.4		-40.9	0.000082	H	
2580	-55.0	34.6		33.3	8.0		-45.7	0.000027	H	
3440	-59.3	35.8		33.6	8.1		-49.0	0.000013	H	
4300	-63.0	35.2		33.2	7.9		-53.1	0.000005	H	NOISE FLOOR
5160	-62.5	36.3		32.8	9.1		-50.0	0.000010	H	NOISE FLOOR
6020	-63.7	36.6		32.0	9.5		-49.6	0.000011	H	NOISE FLOOR
6880	-66.0	37.8		32.8	10.1		-50.8	0.000008	H	NOISE FLOOR
7740	-65.5	39.8		33.4	9.4		-49.7	0.000011	H	NOISE FLOOR
8600	-63.7	41.8		34.4	9.9		-46.3	0.000023	H	NOISE FLOOR

 Notes: SCANNED TO THE TENTH HARMONIC OF CARRIER
 CHECKED THE AXIS - WORST CASE LYING FLAT

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Photographs of Test Setup

FRONT VIEW



REAR VIEW



EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Section 7. Frequency Stability

NAME OF TEST: Frequency Stability	PARA. NO.: 2.995
TESTED BY: Tom Tidwell & Debbie Jensen	DATE:

Test Results: Complies/Does Not Comply.

Measurement Data: See attached tables.

Not Applicable

EQUIPMENT: InCell SMR Repeater**PROJECT NO.:** 1L0025RUS1**Section 8. Test Equipment List**

Nemko ID	Description	Manufacturer Model Number	Serial Number	Calibration Date
1036	SPECTRUM ANALYZER	ROHDE & SCHWARZ FSEK30	830844/006	06/14/99 2 Yr Cycle
1464	Spectrum analyzer	Hewlett Packard 8563E	3551A04428	01/02/01 2 Yr Cycle
1484	Cable 2.0-18.0 Ghz	Storm PR90-010-072	N/A	05/25/00
1485	Cable 2.0-18.0 Ghz	Storm PR90-010-216	N/A	05/25/00
1082	CABLE 2m	Astrolab 32027-2-29094-72TC	N/A	05/23/00
1016	AMPLIFIER	HEWLETT PACKARD 8449A	2749A00159	05/24/00
1475	20db Attenuator DC 18 Ghz	MCL Inc. BW-S20W3	NONE	CBU
993	Horn antenna	A.H. Systems SAS-200/571	XXX	07/16/99 2 Yr Cycle

Annex A - Test Methodologies

EQUIPMENT: InCell SMR Repeater**PROJECT NO.:** 1L0025RUS1**NAME OF TEST: RF Power Output****PARA. NO.: 2.985**

Minimum Standard: Para. No. 90.205(a). The maximum allowable station ERP is dependent upon the stations HAAT and required service area and will be authorized in accordance with Table 1 of 90.205(d).

Method Of Measurement:Detachable Antenna:

The peak power at antenna terminals is measured using an in-line peak power meter. Power output is measured with the maximum rated input level.

Integral Antenna:

If the antenna is not detachable from the circuit then the Peak Power Output is derived from the peak radiated field strength of the fundamental emission by using the plane wave relation $GP/4\pi R^2 = E^2/120\pi$ and proceeding as follows:

$$P = \frac{E^2 R^2}{30G} = \frac{E^2 3^2}{30G}$$

where,

P = the equivalent isotropic radiated power in watts

E = the maximum measured field strength in V/m

R = the measurement range (3 meters)

G = the numeric gain of the transmit antenna in relation to an isotropic radiator

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

NAME OF TEST: Spurious Emissions at Antenna Terminals	PARA. NO.: 2.991
--	-------------------------

Test Method: RBW: 1% of emission bandwidth in the 0 - 1 GHz range.
1 MHz at frequencies above 1 GHz.

VBW: \Rightarrow RBW

The spectrum is searched up to 10 times the fundamental frequency.

EQUIPMENT: InCell SMR Repeater**PROJECT NO.:** 1L0025RUS1**NAME OF TEST: Occupied Bandwidth****PARA. NO.: 2.989****Minimum Standard:** Para. No. 90.210, see table 1 below for applicable mask.**Table 1**

Frequency Band (MHz)	Mask for equipment with Low Pass Filter	Mask for equipment without Low Pass Filter
Below 25	A or B	A or C
25 - 50	B	C
72 - 76	B	C
150 - 174	B, D or E	C, D or E
150 Paging only	B	C
220 - 222	F	F
421 - 512	B, D or E	C, D or E
450 paging only	B	H
806 - 821/ 851 - 866	B	G
821 - 824/ 866 - 869	B	H
896 - 901/ 935 - 940	I	J
902 - 928	K	K
929 - 930	B	G
Above 940	B	C
All other bands	B	C

EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

NAME OF TEST: Field Strength of Spurious	PARA. NO.: 2.993
---	-------------------------

Minimum Standard: Para. No. 90.210, see table 1 for applicable mask.

Test Method: TIA/EIA-603-1992, Section 2.2.12

The antenna substitution method was used to determine the equivalent radiated power at spurious frequencies. The spurious emissions were measured at a distance of 3 meters. The EUT was then replaced with a reference substitution antenna with a known gain referenced to a dipole. This antenna was fed with a signal at the spurious frequency. The level of the signal was adjusted to repeat the previously measured level. The resulting erp is the signal level fed to the reference antenna corrected for gain referenced to a dipole.

EQUIPMENT: InCell SMR Repeater**PROJECT NO.:** 1L0025RUS1**NAME OF TEST: Frequency Stability****PARA. NO.: 2.995**

Minimum Standard: Para. No. 990.213. The transmitter carrier frequency shall remain within the assigned frequency below in ppm.

Table 2


Frequency Band (MHz)	Fixed And Base Stations	Mobile Stations	
		> 2 Watts o/p pwr	< 2 Watts o/p pwr
Below 25	100	100	200
25 - 50	20	20	50
72 - 76	5	-	50
150 - 174	5	5	5
220 - 222	0.1	1.5	1.5
421 - 512	2.5	5	5
806 - 821	1.5	2.5	2.5
821 - 824	1.0	1.5	15
851 - 866	1.5	2.5	2.5
866 - 869	1.0	1.5	1.5
869 - 901	0.1	1.5	1.5
902 - 928	2.5	2.5	2.5
929 - 930	1.5	-	-
935 - 940	0.1	1.5	1.5
1427 - 1435	300	300	300
Above 2450	-	-	-

Annex B - Test Diagrams


EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Para. No. 2.985 - R.F. Power Output




Para. No. 2.989 - Occupied Bandwidth




EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Para. No. 2.991 - Spurious Emissions at Antenna Terminals



Para. No. 2.993 - Field Strength of Spurious Radiation



EQUIPMENT: InCell SMR Repeater

PROJECT NO.: 1L0025RUS1

Para. No. 2.995 - Frequency Stability

