

Test Location: CKC Laboratories, Inc. • 1653 Los Viboras Rd., Site A • Hollister, Ca 95023 • (831) 637-0485

Customer: **Davis Instruments**

Specification: **FCC 15.249(a)**

Work Order #: **72312**

Date: Fri Aug-06-1999

Test Type: **Maximized Emissions**

Time: 14:38:48

Equipment: **Weather Data Telemetry**

Sequence#: 6

Manufacturer: Davis Instruments

Tested By: Wes Norris

Model: 7617

S/N: Prototype

Equipment Under Test (* = EUT):

Function	Manufacturer	Model #	S/N
Weather Data Telemetry*	Davis Instruments	7617	Prototype

Support Devices:

Function	Manufacturer	Model #	S/N
Weather Console	Davis Instruments	7425	WC80921B67
PC Link	Davis Instruments	7862	LC90802A32

Test Conditions / Notes:

The EUT is fully operational, with Wind Vane and Rain Collector connected. The EUT is transmitting continuously, at full power, in CW Mode. The EUT is receiving its power from the AC Adaptor, which is powered from a 115V/60Hz source. The on time of the transmitter in a 100ms period was measured. This on time divided by the 100ms period is the duty cycle. A 20Log(duty cycle) calculation is then performed and this factor (not to exceed 20dB) is then taken into consideration. This method is specified in CFR 47 Section 15.35(c).

Measurement Data: Reading listed by order taken. Test Distance: 3 Meters

#	Freq MHz	Rdng dBμV	AMP LOG CABLE 15.35				Dist Table	Corr dBμV/m	Spec dBμV/m	Margin dB	Polar Ant
			dB	dB	dB	dB					
1	916.513M	79.1	-27.1	+22.5	+4.8	+0.0	+0.0	79.3	93.9	-14.6	Vert
2	916.510M	71.3	-27.1	+22.5	+4.8	+0.0	+0.0	71.5	93.9	-22.4	Horiz
3	916.522M	79.1	-27.1	+22.5	+4.8	-20.0	+0.0	59.3	93.9	-34.6	Vert
Ave											
4	916.523M	71.3	-27.1	+22.5	+4.8	-20.0	+0.0	51.5	93.9	-42.4	Horiz
Ave											

Test Location: CKC Laboratories, Inc. • 1653 Los Viboras Rd., Site A • Hollister, Ca 95023 • (831) 637-0485

Customer: **Davis Instruments**
 Specification: **FCC 15.249(C) / 15.209**
 Work Order #: **72312**
 Test Type: **Maximized Emissions**
 Equipment: **Weather Data Telemetry**
 Manufacturer: Davis Instruments
 Model: 7617
 S/N: Prototype

Date: Mon Oct-25-1999
 Time: 07:19:04
 Sequence#: 2
 Tested By: Wes Norris

Equipment Under Test (* = EUT):

Function	Manufacturer	Model #	S/N
Weather Data Telemetry*	Davis Instruments	7617	Prototype

Support Devices:

Function	Manufacturer	Model #	S/N
Weather Console	Davis Instruments	7425	WC80921B67
PC Link	Davis Instruments	7862	LC90802A32
AC Adaptor	Ablex	7916	N/A

Test Conditions / Notes:

The EUT is fully operational, receiving weather data from the Weather Console. The EUT is transmitting continuously, at full power, in CW Mode. The EUT is receiving its power from the Weather Console, which is powered from the AC Adaptor, which is powered from a 115V/60Hz source. The on time of the transmitter in a 100ms period was measured. This on time divided by the 100ms period is the duty cycle. A 20Log(duty cycle) calculation is then performed and this factor (not to exceed 20dB) is then taken into consideration. This method is specified in CFR 47 Section 15.35(c).

Measurement Data: Reading listed by margin. Test Distance: 3 Meters

#	Freq MHz	Rdng dBμV	Horn 15.35 dB	Amp_2 dB	1-12. dB	1-12. dB	Dist Table	Corr dBμV/m	Spec dBμV/m	Margin dB	Polar Ant
1	1833.000M See #7 for average	73.9	+26.5 +0.0	-38.6	+0.3	+3.9	+0.0	66.0	54.0	+12.0	Horiz
2	1833.000M See #9 for average	66.8	+26.5 +0.0	-38.6	+0.3	+3.9	+0.0	58.9	54.0	+4.9	Vert
3	5499.000M See #17 for average	51.2	+34.9 +0.0	-39.9	+0.4	+7.3	+0.0	53.9	54.0	-0.1	Vert
4	5499.000M See #19 for average	50.5	+34.9 +0.0	-39.9	+0.4	+7.3	+0.0	53.2	54.0	-0.8	Horiz
5	6415.500M See #21 for average	47.7	+35.4 +0.0	-40.3	+0.6	+7.9	+0.0	51.3	54.0	-2.7	Vert
6	6415.500M See #22 for average	46.0	+35.4 +0.0	-40.3	+0.6	+7.9	+0.0	49.6	54.0	-4.4	Horiz
7	1833.000M Ave	73.9	+26.5 -20.0	-38.6	+0.3	+3.9	+0.0	46.0	54.0	-8.0	Horiz
8	3666.000M	62.5	+32.4 -20.0	-38.9	+0.5	+5.8	+0.0	42.3	54.0	-11.7	Horiz
9	1833.000M Ave	66.8	+26.5 -20.0	-38.6	+0.3	+3.9	+0.0	38.9	54.0	-15.1	Vert
10	9165.000M	47.8	+38.5 -20.0	-39.0	+0.6	+9.4	+0.0	37.3	54.0	-16.7	Vert

11	4582.500M	57.1	+32.3 -20.0	-39.7	+0.6	+6.6	+0.0	36.9	54.0	-17.1	Horiz
12	9165.100M	46.5	+38.5 -20.0	-39.0	+0.6	+9.4	+0.0	36.0	54.0	-18.0	Horiz
13	4582.500M	55.9	+32.3 -20.0	-39.7	+0.6	+6.6	+0.0	35.7	54.0	-18.3	Vert
14	7332.000M	49.0	+36.6 -20.0	-39.2	+0.3	+8.3	+0.0	35.0	54.0	-19.0	Vert
15	8248.500M	47.2	+37.6 -20.0	-40.2	+0.8	+9.1	+0.0	34.5	54.0	-19.5	Horiz
16	8248.500M	46.8	+37.6 -20.0	-40.2	+0.8	+9.1	+0.0	34.1	54.0	-19.9	Vert
17	5499.000M Ave	51.2	+34.9 -20.0	-39.9	+0.4	+7.3	+0.0	33.9	54.0	-20.1	Vert
18	7332.000M	47.3	+36.6 -20.0	-39.2	+0.3	+8.3	+0.0	33.3	54.0	-20.7	Horiz
19	5499.000M Ave	50.5	+34.9 -20.0	-39.9	+0.4	+7.3	+0.0	33.2	54.0	-20.8	Horiz
20	3666.000M	52.3	+32.4 -20.0	-38.9	+0.5	+5.8	+0.0	32.1	54.0	-21.9	Vert
21	6415.500M Ave	47.7	+35.4 -20.0	-40.3	+0.6	+7.9	+0.0	31.3	54.0	-22.7	Vert
22	6415.500M Ave	46.0	+35.4 -20.0	-40.3	+0.6	+7.9	+0.0	29.6	54.0	-24.4	Horiz
23	2749.500M	52.0	+29.7 -20.0	-37.6	+0.4	+5.0	+0.0	29.5	54.0	-24.5	Horiz
24	2749.500M	49.9	+29.7 -20.0	-37.6	+0.4	+5.0	+0.0	27.4	54.0	-26.6	Vert