


Any Alternative Parts MUST be approved by Customer.



MUST BE CERTIFIED RoHS - EU Directive 2002/95/EC
Homogenous weight percentage must be less than: Lead<0.1%, Hex Chromium<0.1%, Mercury<0.1%, Polybro.Biphenyls<0.1%, Polybro.Diphenyl Ethers<0.1%, Cadmium<0.01%.

NOTES:

1. Hazardous Substances Specification (HSS)
MCV of hazardous substances in homogeneous material meet: PE-HSS-1001
2. Color:
 - Film color: White
 - Print text color: Black
3. Thickness: 0.07 +/-0.01mm
4. Temperature rating of -20degC to +85degC.
5. Label will be applied to plastic surface ABS PC.
6. Label adhesive required to sustain IP55 water fall to applied label.
7. For on line printing, all text shown in red shall be unique to each label printed (text color will be black).
IRIDIUM-12345 :WiFi SSID number
15digit : IMEI of internal 9523 module
APM12345: Serial number from Maxwell uProcessor
code128 Barcode: Serial number in barcode format
8. Barcode artwork only for reference, add barcode to each label, reference dimension of barcode
3mm x ~19mm



Scale* 2:1	Roughness	Tolerance unless otherwise stated +/- 0.2mm		Original Sheet Size* A4	
Units mm Projection 3rd. Angle 	Material Fasson® 2 Mil White Polyester TC/S333 (Spec# 72825)	Treatment Finish		BEAM P/N: LBLSP0087	
Approved	Date	Maxwell Device Label		Rev 08	Date 08-May-2015
1				Sheet 1 Of 1 Sheets	
2					
3					
		Drawn: GI	Date: 27 Jun 2013	Checked: SP 08/06/2015	
		Beam Communications P/L ABN 97 103 107 919		8 Anzed Court, Mulgrave Victoria 3170 AUSTRALIA	

