| & Partn<br>Engin             | Calibration Laboratory of Schmid<br>A Partner<br>Engineering AG<br>eughausstrasse 43, 8004 Zurich, Switzerland |   |   |                        |       |                           |
|------------------------------|--|---|---|------------------------|-------|---------------------------|
| The Swiss                    |  | ion Service (SAS)<br>is one of the signatorie<br>cognition of calibration               |   |                        | Ac    | creditation No.: SCS 0108 |
| Client                       | UL USA<br>Fremont, USA   |   |   | Certificate N          | No. ( | CD1880V3-1159_Mar23       |
| CALI                         | BRATION C  | ERTIFICATI  |   |                        | -114  |                           |
| Object                       |  | CD1880V3 - SN:  | 1159                                    |                        |       |                           |
| Calibration                  | procedure(s)   | QA CAL-20.v7<br>Calibration Proce   | dure for Validat                        | ion Sources in         | air   |                           |
| Calibration                  | date:  | March 15, 2023  |   |                        |       |                           |
| All calibrati<br>Calibration | ons have been conducte<br>Equipment used (M&TE   | ainties with confidence pr<br>ed in the closed laborator<br>E critical for calibration) |   |                        |       |                           |
| Primary Sta                  |  | ID #  | Cal Date (Certificat                    |                        |       | Scheduled Calibration     |
| Power met                    |  | SN: 104778  | 04-Apr-22 (No. 217                      | ,                      |       | Apr-23                    |
|                              | sor NRP-Z91  | SN: 103244  | 04-Apr-22 (No. 217                      | ,                      |       | Apr-23                    |
|                              | sor NRP-Z91  | SN: 103245  | 04-Apr-22 (No. 217                      |                        |       | Apr-23                    |
|                              | 20 dB Attenuator   | SN: BH9394 (20k)  | 04-Apr-22 (No. 217                      |                        |       | Apr-23                    |
|                              | match combination  | SN: 310982 / 06327  | 04-Apr-22 (No. 217                      | , ,                    |       | Apr-23                    |
| Probe EF3I<br>DAE4           | JV3  | SN: 4013<br>SN: 781   | 30-Dec-22 (No. EF<br>03-Jan-23 (No. DAI |                        |       | Dec-23<br>Jan-24          |
| Secondary                    |  | ID#   | Check Date (in hou                      | - 14                   |       | Scheduled Check           |
|                              | er Agilent 4419B   | SN: GB42420191  | 09-Oct-09 (in house                     | ,                      |       | In house check: Oct-23    |
|                              | SOF HP E4412A  | SN: US38485102  | 05-Jan-10 (in house                     |                        |       | In house check: Oct-23    |
|                              | or HP 8482A  | SN: US37295597  | 09-Oct-09 (in house                     |                        |       | In house check: Oct-23    |
| -                            | or R&S SMT-06  | SN: 837633/005  | 10-Jan-19 (in house check Oct-20)       |                        |       | In house check: Oct-23    |
| Network An                   | alyzer Agilent E8358A  | SN: US41080477  | 31-Mar-14 (in house                     | e cneck Oct-22)        |       | In house check: Oct-24    |
|                              |  | Name  | Functio                                 |                        |       | Signature                 |
| Calibrated b                 | by:  | Aidonia Georgiadou  | Labora                                  | tory Technician        |       | Atzp                      |
| Approved b                   | y:   | Sven Kühn   | Technic                                 | cal Manager            |       | 5.5                       |
| <b>T</b> L:- ···             | 11   |   |   |                        |       | Issued: March 16, 2023    |
| i his calibrat               | tion certificate shall not b   | pe reproduced except in f   | ull without written app                 | proval of the laborato | ory.  |                           |

Calibration Laboratory of

Schmid & Partner Engineering AG Zeughausstrasse 43, 8004 Zurich, Switzerland



Schweizerischer Kalibrierdienst

Service suisse d'étalonnage

S

С

S

Servizio svizzero di taratura

Swiss Calibration Service

Accreditation No.: SCS 0108

Accredited by the Swiss Accreditation Service (SAS) The Swiss Accreditation Service is one of the signatories to the EA Multilateral Agreement for the recognition of calibration certificates

#### References

 [1] ANSI-C63.19-2019 (ANSI-C63.19-2011) American National Standard, Methods of Measurement of Compatibility between Wireless Communications Devices and Hearing Aids.

#### Methods Applied and Interpretation of Parameters:

- Coordinate System: y-axis is in the direction of the dipole arms. z-axis is from the basis of the antenna (mounted on the table) towards its feed point between the two dipole arms. x-axis is normal to the other axes. In coincidence with the standards [1], the measurement planes (probe sensor center) are selected to be at a distance of 15 mm above the top metal edge of the dipole arms.
- *Measurement Conditions:* Further details are available from the hardcopies at the end of the certificate. All figures stated in the certificate are valid at the frequency indicated. The forward power to the dipole connector is set with a calibrated power meter connected and monitored with an auxiliary power meter connected to a directional coupler. While the dipole under test is connected, the forward power is adjusted to the same level.
- Antenna Positioning: The dipole is mounted on a HAC Test Arch phantom using the matching dipole positioner with the arms horizontal and the feeding cable coming from the floor. The measurements are performed in a shielded room with absorbers around the setup to reduce the reflections. It is verified before the mounting of the dipole under the Test Arch phantom, that its arms are perfectly in a line. It is installed on the HAC dipole positioner with its arms parallel below the dielectric reference wire and able to move elastically in vertical direction without changing its relative position to the top center of the Test Arch phantom. The vertical distance to the probe is adjusted after dipole mounting with a DASY5 Surface Check job. Before the measurement, the distance between phantom surface and probe tip is verified. The proper measurement distance is selected by choosing the matching section of the HAC Test Arch phantom with the proper device reference point (upper surface of the dipole) and the matching grid reference point (tip of the probe) considering the probe sensor offset. The vertical distance to the probe is essential for the accuracy.
- Feed Point Impedance and Return Loss: These parameters are measured using a Vector Network Analyzer. The impedance is specified at the SMA connector of the dipole. The influence of reflections was eliminating by applying the averaging function while moving the dipole in the air, at least 70cm away from any obstacles.
- *E-field distribution:* E field is measured in the x-y-plane with an isotropic E-field probe with 100 mW forward power to the antenna feed point. In accordance with [1], the scan area is 20mm wide, its length exceeds the dipole arm length (180 or 90mm). The sensor center is 15 mm (in z) above the metal top of the dipole arms. Two 3D maxima are available near the end of the dipole arms. Assuming the dipole arms are perfectly in one line, the average of these two maxima (in subgrid 2 and subgrid 8) is determined to compensate for any non-parallelity to the measurement plane as well as the sensor displacement. The E-field value stated as calibration value represents the maximum of the interpolated 3D-E-field, in the plane above the dipole surface.

The reported uncertainty of measurement is stated as the standard uncertainty of measurement multiplied by the coverage factor k≈2, which for a normal distribution corresponds to a coverage probability of approximately 95%.

## **Measurement Conditions**

DASY system configuration, as far as not given on page 1.

| DASY Version                       | DASY5                                | V52.10.4 |
|------------------------------------|--------------------------------------|----------|
| Phantom                            | HAC Test Arch                        |          |
| Distance Dipole Top - Probe Center | 15 mm                                |          |
| Scan resolution                    | dx, dy = 5 mm                        |          |
| Frequency                          | 1730 MHz ± 1 MHz<br>1880 MHz ± 1 MHz |          |
| Input power drift                  | < 0.05 dB                            |          |

## Maximum Field values at 1730 MHz

| E-field 15 mm above dipole surface | condition          | Interpolated maximum    |  |
|------------------------------------|--------------------|-------------------------|--|
| Maximum measured above high end    | 100 mW input power | 94.1 V/m = 39.47 dBV/m  |  |
| Maximum measured above low end     | 100 mW input power | 92.9 V/m = 39.36 dBV/m  |  |
| Averaged maximum above arm         | 100 mW input power | 93.5 V/m ± 12.8 % (k=2) |  |

## Maximum Field values at 1880 MHz

| E-field 15 mm above dipole surface | condition          | Interpolated maximum    |  |
|------------------------------------|--------------------|-------------------------|--|
| Maximum measured above high end    | 100 mW input power | 86.3 V/m = 38.72 dBV/m  |  |
| Maximum measured above low end     | 100 mW input power | 85.2 V/m = 38.61 dBV/m  |  |
| Averaged maximum above arm         | 100 mW input power | 85.7 V/m ± 12.8 % (k=2) |  |

## Appendix (Additional assessments outside the scope of SCS 0108)

### **Antenna Parameters**

Nominal Frequencies

| Frequency | Return Loss | Impedance        |
|-----------|-------------|------------------|
| 1730 MHz  | 35.1 dB     | 49.3 Ω + 1.6 jΩ  |
| 1880 MHz  | 18.0 dB     | 55.0 Ω + 12.3 jΩ |
| 1900 MHz  | 18.4 dB     | 57.9 Ω + 10.3 jΩ |
| 1950 MHz  | 22.2 dB     | 58.1 Ω + 1.8 jΩ  |
| 2000 MHz  | 26.3 dB     | 50.0 Ω + 4.8 jΩ  |

#### 3.2 Antenna Design and Handling


The calibration dipole has a symmetric geometry with a built-in two stub matching network, which leads to the enhanced bandwidth.

The dipole is built of standard semirigid coaxial cable. The internal matching line is open ended. The antenna is therefore open for DC signals.

Do not apply force to dipole arms, as they are liable to bend. The soldered connections near the feedpoint may be damaged. After excessive mechanical stress or overheating, check the impedance characteristics to ensure that the internal matching network is not affected.

After long term use with 40W radiated power, only a slight warming of the dipole near the feedpoint can be measured.

### Impedance Measurement Plot



Test Laboratory: SPEAG Lab2

#### DUT: HAC Dipole 1880 MHz; Type: CD1880V3; Serial: CD1880V3 - SN: 1159

Communication System: UID 0 - CW ; Frequency: 1880 MHz, Frequency: 1730 MHz Medium parameters used:  $\sigma$  = 0 S/m,  $\epsilon_r$  = 1;  $\rho$  = 0 kg/m<sup>3</sup> Phantom section: RF Section Measurement Standard: DASY5 (IEEE/IEC/ANSI C63.19-2011)

DASY52 Configuration:

- Probe: EF3DV3 SN4013; ConvF(1, 1, 1) @ 1880 MHz, ConvF(1, 1, 1) @ 1730 MHz; Calibrated: 30.12.2022
- Sensor-Surface: (Fix Surface)
- Electronics: DAE4 Sn781; Calibrated: 03.01.2023
- Phantom: HAC Test Arch with AMCC; Type: SD HAC P01 BA; Serial: 1070
- DASY52 52.10.4(1535); SEMCAD X 14.6.14(7501)

### Dipole E-Field measurement @ 1880MHz/E-Scan - 1880MHz d=15mm/Hearing Aid Compatibility Test (41x181x1):

Interpolated grid: dx=0.5000 mm, dy=0.5000 mm Device Reference Point: 0, 0, -6.3 mm Reference Value = 155.2 V/m; Power Drift = -0.02 dB Applied MIF = 0.00 dB RF audio interference level = 38.71 dBV/m **Emission category: M2** 

| MIF | scaled | E-field |
|-----|--------|---------|
|     |        |         |


| Grid 1 <b>M2</b> | Grid 2 <b>M2</b> | Grid 3 <b>M2</b> |
|------------------|------------------|------------------|
| 38.55 dBV/m      | 38.61 dBV/m      | 38.31 dBV/m      |
| Grid 4 M2        | Grid 5 M2        | Grid 6 <b>M2</b> |
| 35.97 dBV/m      | 35.99 dBV/m      | 35.84 dBV/m      |
| Grid 7 <b>M2</b> | Grid 8 <b>M2</b> | Grid 9 <b>M2</b> |
| 38.64 dBV/m      | 38.72 dBV/m      | 38.39 dBV/m      |

## Dipole E-Field measurement @ 1880MHz/E-Scan - 1730MHz d=15mm/Hearing Aid Compatibility Test (41x181x1):

Interpolated grid: dx=0.5000 mm, dy=0.5000 mm Device Reference Point: 0, 0, -6.3 mm Reference Value = 169.8 V/m; Power Drift = 0.01 dB Applied MIF = 0.00 dB RF audio interference level = 39.47 dBV/m **Emission category: M2** 

MIF scaled E-field

|                  | Grid 2 <b>M2</b> |                  |
|------------------|------------------|------------------|
| 39.29 dBV/m      | 39.36 aBV/m      | 39.07 dBV/m      |
| Grid 4 M2        | Grid 5 M2        | Grid 6 <b>M2</b> |
| 36.72 dBV/m      | 36.75 dBV/m      | 36.56 dBV/m      |
| Grid 7 <b>M2</b> | Grid 8 <b>M2</b> | Grid 9 <b>M2</b> |
| 39.39 dBV/m      | 39.47 dBV/m      | 39.12 dBV/m      |



0 dB = 86.25 V/m = 38.72 dBV/m



# Dipole Impedance Measurement

| Equipment Location            | Equipment | Model Name | Date of      |
|-------------------------------|-----------|------------|--------------|
|                               | Name      |            | Verification |
| UL Verification Services Inc. | Dipole    | CD1880V3-  | January 29,  |
| 47173 Benicia Street          | Antenna   | 1159       | 2024         |
| Fremont, CA 94538, U.S.A.     |           |            |              |
|                               |           |            |              |


| Number: | Check List:               | Result: |
|---------|---------------------------|---------|
| 1       | Visual Inspection         | Pass    |
| 2       | Return/Loss and Impedance | Pass    |
| 3       | Dipole Arms               | Pass    |

| Equipment List:                   |           |  |
|-----------------------------------|-----------|--|
| Equipment Name: Calibration Date: |           |  |
| R&S Vector Network Analyzer       | 2/18/2024 |  |
| ZV-Z135 Calibration Kit           | 3/10/2024 |  |



# Dipole Impedance Measurement


## 1) Photo of Dipole



• The connector of dipole contains no abnormalities.



## 2) Impedance and Return/Loss




02:35:44 06.02.2024

• Return/Loss is greater than the -20 dB cutoff and Impedance is within 5  $\Omega$  of previous value.



# Dipole Impedance Measurement

## 3) Dipole Arms



- The center red line indicates that the arms of the dipole fall within  $\pm 2^\circ$